Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
152	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Ground Floor	Sqm	156.00	1842.00	Rupees One Thousand Eight Hundred Forty Two Only
153	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. First Floor	Sqm	117.40	1844.00	Rupees One Thousand Eight Hundred Forty Four Only
154	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.Second Floor	Sqm	78.50	1846.00	Rupees One Thousand Eight Hundred Forty Six Only
155	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.-Third Floor	Sqm	78.50	1848.00	Rupees One Thousand Eight Hundred Forty Eight Only
156	Providing and laying heavy duty cobble stones 75mm thick inter lock pavers, using cement and course sand for manufacture of block of approved size, shape and colur with a minimum compressive strength of 281 Kg per Sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in betwen joints, final compaction of paver surface joints its final level, including cost of materials, labour and HOM of machineries complete as per specification.	Sqm	180.00	1204.00	Rupees One Thousand Two Hundred Four Only
157	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - First Floor	Cum	6.00	2361.00	Rupees Two Thousand Three Hundred Sixty One Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
158	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - Second Floor	Cum	6.00	2361.00	Rupees Two Thousand Three Hundred Sixty One Only
159	Providing and laying Cinder concrete in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - Third Floor	Cum	6.00	2361.00	Rupees Two Thousand Three Hundred Sixty One Only
160	Providing INTEGRAL CRYSTALINE Waterproofing treatment to the sunken portion of toilets. Using Crystalline Slurry of approved make @ 1.40 kg per SQM in two coats (0.7 Kg per coat) confirming to ASTM S 1202 & DINV 18998 standards.	Sqm	84.00	596.00	Rupees Five Hundred Ninety Six Only
161	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification	Sqm	450.00	732.00	Rupees Seven Hundred Thirty Two Only
162	Providing TEAK WOOD frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.30	230805.00	Rupees Two Lakh Thirty Thousand Eight Hundred Five Only
163	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Ground Floor	Cum	0.80	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
164	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - First Floor	Cum	0.15	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
165	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Second Floor	Cum	0.15	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
166	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - Third Floor	Cum	0.15	79355.00	Rupees Seventy Nine Thousand Three Hundred Fifty Five Only
167	KSRB 9.5-1 : Providing and fixing in position fully panelled Teak wood shutters for doors, with styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawingand panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqm	4.80	10304.00	Rupees Ten Thousand Three Hundred Four Only
168	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - Ground Floor	Sqm	24.80	3809.00	Rupees Three Thousand Eight Hundred Nine Only
169	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - First Floor	Sqm	6.30	3809.00	Rupees Three Thousand Eight Hundred Nine Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part I) 1991. From manufacturer (Factory) complete as per specification. Second Floor	Sqm	6.30	3809.00	Rupees Three Thousand Eight Hundred Nine Onl
171	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part I) 1991. From manufacturer (Factory) complete as per specification. Third Floor	Sqm	6.30	3809.00	Rupees Three Thousand Eight Hundred Nine Onl
172	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 02x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m. shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenoned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gattes, including cutting masonry or concrete and making good the original surface using cement mortar. Ground Floor	Sqm	71.40	7697.00	Rupees Seven Thousand Six Hundred Ninety Seven Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl. No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
173	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m. sides and top sections 1.3 mm. thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m. shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc., providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - First Floor	Sqm	41.00	7703.00	Rupees Seven Thousand Seven Hundred Three Only
174	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m. sides and top sections 1.3 mm. thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m. shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc., providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Second Floor	Sqm	41.00	7709.00	Rupees Seven Thousand Seven Hundred Nine Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
175	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm. thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Third Floor	Sqm	41.00	7716.00	Rupees Seven Thousand Seven Hundred Sixteen Only
176	Providing and fixing M.S.grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifictions. Specification No. KBS 7.12 (Considered 18 Kg/sqm)	Kgs	3499.20	103.00	Rupees One Hundred Three Only
177	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. Ground Floor	Sqm	47.30	5007.00	Rupees Five Thousand Seven Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
178	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. -First Floor	Sqm	18.90	5013.00	Rupees Five Thousand Thirteen Only
179	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. -Second Floor	Sqm	18.90	5019.00	Rupees Five Thousand Nineteen Only
180	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. -Third Floor	Sqm	18.90	5025.00	Rupees Five Thousand Twenty Five Only
181	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications.	Sqm	92.40	3552.00	Rupees Three Thousand Five Hundred Fifty Two Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
182	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Ground Floor	Rmtr	39.90	596.00	Rupees Five Hundred Ninety Six Only
183	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - First Floor	Rmtr	34.20	602.00	Rupees Six Hundred Two Only
184	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Second Floor	Rmtr	34.20	608.00	Rupees Six Hundred Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
185	Providing and fixing 65mmx90mm GRP Doorframe fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - Third Floor	Rmtr	34.20	615.00	Rupees Six Hundred Fifteen Only
186	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Ground Floor	Sqm	11.10	3973.00	Rupees Three Thousand Nine Hundred Seventy Three Only
187	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - First Floor	Sqm	9.50	3979.00	Rupees Three Thousand Nine Hundred Seventy Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
8	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Second Floor	Sqm	9.50	3985.00	Rupees Three Thousand Nine Hundred Eighty Five Only
89	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural - Third Floor	Sqm	9.50	3991.00	Rupees Three Thousand Nine Hundred Ninety One Only
190	Providing and fixing 1mm thick M.S. sheet garage door with frame and diagonal braces of size 40x40x6 mm angle Iron, 3.15mm thickM.S. Gusset plates at the junctions and corners, with handles, stoppers and locking arrangements etc., including applying a priming coat of redlead paint cost of materials, labour, HOM of machinery complete as perspecifications. Double leaf door of size 2.4x2.4m	Sqm	4.20	2920.00	Rupees Two Thousand Nine Hundred Twenty Only
191	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Ground floor	Nos	12.00	1308.00	Rupees One Thousand Three Hundred Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
192	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - First floor	Nos	2.00	1312.00	Rupees One Thousand Three Hundred Twelve Only
193	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Second floor	Nos	2.00	1316.00	Rupees One Thousand Three Hundred Sixteen Only
194	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Third floor	Nos	2.00	1320.00	Rupees One Thousand Three Hundred Twenty Only
195	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications - Terrrace floor	Nos	1.00	1323.00	Rupees One Thousand Three Hundred Twenty Three Only
196	Fixtures-Providing and fixing fixtures for Door incluidng screws etc., complete as per specification and as per the directions by the Engineer in charge For Chromium plated Brass butt hinges (heavy) type 75x65x4 mm weighing not less than 200gms	Nos	21.00	115.00	Rupees One Hundred Fifteen Only
197	Chromium plated Brass handles 125 mm with plate 175 x32 mm	Nos	17.00	201.00	Rupees Two Hundred One Only
198	Chromium plated Brass mortice latch and lock 100x65 mm with 6 levers and a pair of brass lever handles	Nos	5.00	569.00	Rupees Five Hundred Sixty Nine Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
	Brass tower bolt (barrel type) 250x10 mm	Nos	17.00	287.00	Rupees Two Hundred Eighty Seven Only
200	Brass tower bolt (barrel type) 150x10 mm	Nos	25.00	172.00	Rupees One Hundred Seventy Two Only
01	Chromium plated Brass screws 20 mm	Nos	580.00	2.00	Rupees Two Only
02	Hydraulic door clouser - aluminium body	Nos	13.00	1517.00	Rupees One Thousand Five Hundred Seventeen Only
03	Brass 150 mm floor door stopper weighing not less than 0.357kg	Nos	4.00	195.00	Rupees One Hundred Ninety Five Only
04	Providing and fixing Stainless steel 304 Grade for staircase railing, Balconys Ramps with hand rails 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges etc., complete as per specification	Sqm	108.90	7631.00	Rupees Seven Thousand Six Hundred Thirty One Only
205	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should bethoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification.	Sqm	16.00	3642.00	Rupees Three Thousand Six Hundred Forty Two Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
206	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for straight Brick/Rcc/stone walls & coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel should consist of 2.5 mm thermoplastic core of antitoxic LDPE sandwiched between 0.25 skins thick aluminium sheet making a total panel thickness of 3mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done using weather sealant of Dow Corning 789 with necessary rods etc., complete	Sqm	110.25	5608.00	Rupees Five Thousand Six Hundred Eight Only
207	Providing,fabricating and fixing of stick type structural glazing using alluminium extrusions of 63.5mmx58.00mmx2.25mm of 1.73 kgs/mtr for vertical and horizantal members and 63.5mmx38.1x1.33mm of 0.759kg/mtr, as outer franme with electro anodized paint coated block finishing,using 6mm thick imported glass reflective hard coated ocean blue raw glass with allneccessary accssories like ultra glass silicon sealent of space tape,masking tape ,galvanized anchaor bolt, machine screws,6mm thick M.S.angle 50mmx150mmx6mm M.S.galvanized L Brackets, structural sealent setting clocks, fasteners,wall connection etc., complete.	Sqm	156.00	7295.00	Rupees Seven Thousand Two Hundred Ninety Five Only
208	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification	Sqm	105.00	6485.00	Rupees Six Thousand Four Hundred Eighty Five Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
	SSR 8.7-1 :Providing and fixing in position 12mm thick plaster of paris (Gypsum anhydrous) for ceiling reinforced with hessian cloth flat surface upto a height of 5 m above floor level over aluminium 25mm / 6mm with 10mm gap in between and reinforced with rabbit wire mesh fixed to metal frames including cost of materials, labour, curing complete as per specifications.	Sqm	580.00	1178.00	Rupees One Thousand One Hundred Seventy Eight Only
210	Providing, fabricating and fixing partition frame work consisting of 50mm x 50mm sal wood frame work at spacing not exceeding 600mm c/c fixed to the bottom and ceiling, the partition shall be skinned on both sides using 12mm thick commercial plywood of approved brand termite and water resistance, and top covered with 4mm thick approved quality veneer finished with melamine polish, complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment as per specification.	Sqm	130.41	10180.00	Rupees Ten Thousand One Hundred Eighty Only
211	Providing and fixing Single shutter glass door of 12mm thick frosted toughened glass of approved make (Saint Gobain, Modi float). The door is fixed by using any approved make hardware fitting like patch fitting, pivot, floor machine, locking arrangements and suitable SS door rails with floral glass etching for 1/3 portion of door area etc complete. The rate includes cost of all materials, labour, hire of tools & machineries, as per specification.	Sqm	5.67	13904.00	Rupees Thirteen Thousand Nine Hundred Four Only
212	Providing and fixing Veneer paneling, over the 50mm x 35mm sal wood frame work at spacing not exceeding 600mm c/c fixed to the wall and top covered out of 4mm thick approved quality Veneer, fixed over 12mm thick ply of approved brand, termite and water resistant, finished with melamine polish, complete including cost and conveyance of all materials, labour for all items of work HOM of equipment etc., complete as per specification.	Sqm	52.44	5835.00	Rupees Five Thousand Eight Hundred Thirty Five Only
213	Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grove section 2.683 kg/m and bottom bottom member 114.3 mm x 44.45 mm 3.18 mm thick and 2.6 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick pre laminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and riveted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m from floor level; and	Sqm	108.33	5873.00	Rupees Five Thousand Eight Hundred Seventy Three Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
214	KSEB Z 17 Providing, fabricating, assembling and fixing in position aluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm, section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mm thickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section 49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazing clips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m, aluminium sections cut to length joint mitred corners grinded, the shutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock, pivots, P.V.C. or rubber gasket with 5.5m thick plain glass for top and bottom panel, aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non adherance of mortars or any other sticky materials; the assembled frame fitted with the corner angles, cleats and fitted with screws, raul plugs or	Sqm	5.67	7834.00	Rupees Seven Thousand Eight Hundred Thirty Four Only
215	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials a) Short point upto 3.0M from tapping point to outlet via switch box	Each	110.00	166.00	Rupees One Hundred Sixty Six Only
216	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials b) Medium point above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	198.00	247.00	Rupees Two Hundred Forty Seven Only
217	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials c) Long point above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	136.00	384.00	Rupees Three Hundred Eighty Four Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
218	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials d) Two outlet in a row, above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	15.00	486.00	Rupees Four Hundred Eighty Six Only
219	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet. Point wirig using class A Materials e) Three outlet in a row, above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	5.00	682.00	Rupees Six Hundred Eighty Two Only
220	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 1-3Way	Each	26.00	105.00	Rupees One Hundred Five Only
221	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 6 Way	Each	14.00	139.00	Rupees One Hundred Thirty Nine Only
222	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 8Way	Each	27.00	161.00	Rupees One Hundred Sixty One Only
223	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall - 10-12Way	Each	36.00	183.00	Rupees One Hundred Eighty Three Only
224	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - a)1-3Module	Each	28.00	125.00	Rupees One Hundred Twenty Five Only
225	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box - b)6 Module	Each	14.00	199.00	Rupees One Hundred Ninety Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner